BAR SCHEDULE

Project: 7c9e6f10-2a3b-4c5d-9e8f-1a2b3c4d5e6f

Drawing number: ARRB-P3-BBS-001

Issued: 2026-10-21

Status: Candidate - not for construction

Bars: 297 Total weight: 278.9998 kg

The schedule is data (W2.4); the engine measured the steel it describes.

BAR SCHEDULE (continued)

Mark	Member	Role	Shape	Dia	No.	Length	Weight
C1-MAINS	C1	mains	straight	16.0	4	2920.0	18.435
C1-LINK-1	C1	links	link	8.0	20	880.0	6.9447
C2-MAINS	C2	mains	straight	16.0	4	2920.0	18.435
C2-LINK-1	C2	links	link	8.0	20	880.0	6.9447
C3-MAINS	C3	mains	straight	16.0	4	2920.0	18.435
C3-LINK-1	C3	links	link	8.0	20	880.0	6.9447
C4-MAINS	C4	mains	straight	16.0	4	2920.0	18.435
C4-LINK-1	C4	links	link	8.0	20	880.0	6.9447
B1-MAINS	B1	mains	straight	16.0	4	2920.0	18.435
B1-LINK-1	B1	links	link	8.0	20	1180.0	9.3122
B2-MAINS	B2	mains	straight	16.0	4	2920.0	18.435
B2-LINK-1	B2	links	link	8.0	20	1180.0	9.3122
B3-MAINS	B3	mains	straight	16.0	4	2920.0	18.435
B3-LINK-1	B3	links	link	8.0	20	1180.0	9.3122
S1-MAINS	Slab_1	mains	straight	10.0	2	9220.0	11.369
S1-DIST	Slab_1	distribution	straight	8.0	47	220.0	4.08
F1-MESH-X	F1	mesh	straight	12.0	8	1120.0	7.9548
F1-MESH-Y	F1	mesh	straight	12.0	8	1120.0	7.9548
F1-START	F1	starters	starter	16.0	4	600.0	3.788
F2-MESH-X	F2	mesh	straight	12.0	8	1120.0	7.9548
F2-MESH-Y	F2	mesh	straight	12.0	8	1120.0	7.9548
F2-START	F2	starters	starter	16.0	4	600.0	3.788
F3-MESH-X	F3	mesh	straight	12.0	8	1120.0	7.9548
F3-MESH-Y	F3	mesh	straight	12.0	8	1120.0	7.9548
F3-START	F3	starters	starter	16.0	4	600.0	3.788
F4-MESH-X	F4	mesh	straight	12.0	8	1120.0	7.9548
F4-MESH-Y	F4	mesh	straight	12.0	8	1120.0	7.9548
F4-START	F4	starters	starter	16.0	4	600.0	3.788

TOTALS

Bars: 297

Total weight (kg): 278.9998

Dia 10 mm (kg): 181.4997

Dia 12 mm (kg): 97.5001

ASSUMPTIONS

/phases/foundation/data/rebarCoverMm: 40.0 mm
the rule pack (v0) has no detailing rule; v0 assumes a 40 mm cover

/phases/foundation/data/columnMainDiameterMm: 16.0 mm
the rule pack (v0) has no rebar detailing rule; v0 assumes 16 mm column mains

/phases/foundation/data/linkDiameterMm: 8.0 mm
the rule pack (v0) has no rebar detailing rule; v0 assumes 8 mm links

/phases/foundation/data/linkSpacingMm: 150.0 mm
the rule pack (v0) has no rebar detailing rule; v0 assumes 150 mm link spacing

/phases/foundation/data/footingMeshDiameterMm: 12.0 mm
the rule pack (v0) has no rebar detailing rule; v0 assumes 12 mm footing mesh