BILL OF QUANTITIES

Project: 7c9e6f10-2a3b-4c5d-9e8f-1a2b3c4d5e6f

Document number: ARRB-P3-BOQ-001

Issued: 2026-10-21

Status: Candidate - not for construction

Rate card: dhaka-example-2026-10 (dhaka, status candidate)

Rate source: Illustrative example card (structure demo) (manual)

Effective from: 2026-10-01

Grand total: 156594.3 BDT (9 priced, 2 unpriced)

the quantities are measured from the design; the rates come from the rate card (dhaka-example-2026-10, status candidate)

PHASE: site-excavation

Description	Type	Unit	Qty	Rate	Amount
Excavation (machinery)	machinery	hour	24.491	2800.0	68574.8

the declared excavation prism (293.892 m3) at an assumed 12.0 m3/hour

Subtotal (site-excavation): 68574.8 BDT

PHASE: foundation

Description	Type	Unit	Qty	Rate	Amount
Cement (foundation)	material	bag	72.9	575.0	41917.5
the mix is an assumption, not a pack rule | DEVIATION (cost_risk): Price override: Cement (OPC 43 grade) - 575.00 BDT/bag against 550.00 BDT/bag - ack					
Sand (foundation)	material	cft	17.2044	42.0	722.58
Mason (labour)	labour	day	3.888	950.0	3693.6
Concrete mixer	machinery	day	1.215	3500.0	4252.5
Formwork (foundation)	other	sqm	28.8	-	-
no formwork rate in the v0 card: the line is measured, not priced					

Subtotal (foundation): 50586.18 BDT

PHASE: floor

Description	Type	Unit	Qty	Rate	Amount
Cement (floor)	material	bag	19.8281	575.0	11401.16
the mix is an assumption, not a pack rule | DEVIATION (cost_risk): Price override: Cement (OPC 43 grade) - 575.00 BDT/bag against 550.00 BDT/bag - ack					
Sand (floor)	material	cft	4.6794	42.0	196.53
Steel reinforcement	material	ton	0.279	89000.0	24831.0
the scheduled steel, not an estimate					
Mason (floor, labour)	labour	day	1.0575	950.0	1004.63
Formwork (floor)	other	sqm	17.19	-	-
no formwork rate in the v0 card: the line is measured, not priced					

Subtotal (floor): 37433.32 BDT

TOTALS

Grand total: 156594.3 BDT

Priced lines: 9

Unpriced lines: 2

- unpriced: formwork-foundation

BY PHASE

floor: 37433.32 BDT
foundation: 50586.18 BDT
site-excavation: 68574.8 BDT

BY COST TYPE

labour: 4698.23 BDT
machinery: 72827.3 BDT
material: 79068.77 BDT

DEVIATIONS

dev-001 (approval_risk): 2.4 m against 3.0 m
price-cement-opc-43 (cost_risk): 575.00 BDT/bag against 550.00 BDT/bag